



ITEMS LIST

| Equipment | |
|----------------------------|------------------|
| A. Pod Swing | Ref:J441A |
| B. Combination Swing | Ref:J473A |
| C. Low Platform Roundabout | Ref:J2404A |
| D. Double Perch | Ref:J986A |
| E. Tema Multiplay Unit | Ref:J4051A |
| F. Basic Senior Climber | Ref:J1606A |
| G. Trampoline | Ref:R34-ETP-000A |

| Ancillaries | |
|---|-------------|
| H. 71Lm of 1m High Bowtop Fencing Galvanised | Ref:UKN1000 |
| I. 1m High Prosafe Combination Gate Powdercoated Yellow | Ref:UKN1104 |
| J. 1m High Prosafe Gate Powdercoated Yellow | Ref:UKN1101 |

Groundworks
Area to be surfaced with 160m² of green Rubber Mulch with wetpour wearpads at depths of:

| | |
|---------------------|-----------------------|
| 137m ² | @ 40mm |
| 23m ² | @ 60mm |
| Colour breakdown: | |
| 139.5m ² | @ Green Rubber Mulch |
| 6m ² | @ Light Green wetpour |
| 9.5m ² | @ Red wetpour |
| 5m ² | @ Light Blue wetpour |

Requiring 2m² MOT Type 1 Stone base to aid leveling and surfacing stability where rubber mulch & wetpour is to be laid directly onto grass. Edging with 113Lm of chase cut into surrounding turf.

Item F & G to be surfaced with 68m² of Envirosmart Grassmat

Removals
Removal of existing 71Lm of fencing & Gates.
Removal of existing large MPU, cradle swings, flat swings, 2x springers, small MPU, seesaw & 4x swing barriers.
Removal of 18m² of existing wetpour and associated ground works.

Optional Extras
Post installation inspection has been included as optional extra.

| | |
|-----------------------------|------------------|
| K. Hydraulic Chest Press | Ref:R37-UBX-246B |
| L. Hydraulic Shoulder Press | Ref:R37-UBX-247B |
| M. Hydraulic Squat | Ref:R37-UBX-217B |

To be surfaced with 9m² Envirosmart grassmat.

Proposed Grassmat Safer surfacing is based on a fully established grass site (including a minimum of 150mm of good quality soil and turf).

Mulch price based on a well draining site, any additional drainage required (french drains or soak aways) will be at an additional cost.

Preliminaries have been included within your quotation, these equate to site setup, site storage, delivery, unloading of equipment, site welfare, heras fencing & signage and skips (this can also include supervision where necessary).

Topsoil & Seed watering is the responsibility of others and has not been costed for.

Fencing will be made up from standard straight lengths and installed faceted. If rounded fencing is required this will incur additional costs.

Some images shown are for illustrative purposes only. The quote and items list will show the exact equipment used.

| PRODUCT KEY | | | |
|-------------|--------------|--|----------------|
| | Rubber Mulch | | Topsoil & Seed |
| | Grassmat | | Fencing |
| | Free Fall | | Free Space |
| | Hedging | | |

Victory Park Play Area

Cainscross Parish Council

DATE: 24/10/2019 REF: 1910.24354(VictoryParkPA_CainscrossPC)

REV: - DB: JPS CB: DB

SCALE: 1:200 @ A3

